

page 1

BILL OF QUANTITIES

SUBJECT: Shops and Car Park area

CLIENT: Green Park Business Campus

Date, 04/03/2015

QUANTITY SURVEYOR Arch. Jackie Bell



The Building Company Plc 22 Salehurst Rd - London SE4 1YJ



The Building Company Plc 22 Salehurst Rd - London SE4 1YJ

page 2

Id.Nr. TARIFF	DESCRIPTION OF WORKS	DIMENSIONS					AMOUNTS	
		eq. parts	length	width	H/weight	Quantity	UNIT RATE	TOTAL
	TO COLLECTION							
	MEASURED WORKS							
1 C.05.006A	Concrete work for sub-structure and super-structure (including plinths, beam connections, T-section foundation beams, slabs, slab on grade and all works generally cast in special m installation of iron, formed at the rate of 0,400 m3 of sand, 0,800 m3 of gravel or crushed stone and 250 kg of cement.							
	Block A - Foundation Slab detracting openings	2,00	15,00 1,00	8,000 1,000	0,600 <mark>0,600</mark>	72,00 -1,20		
	Partial m3					70,80		
	Block B - Foundation Slab detracting openings	2,00	20,00 1,00 0,50	10,000 1,000 1,600	0,600 0,600 0,600	120,00 -0,60 -0,96		
	Partial m3					118,44		
	Summing positive values m3 Summing negative values m3					192,00 -2,76		
	SUB TOTAL m3					189,24	83,95	15′886,7
	Partial MEASURED WORKS euro							15′886,7
	TOTAL euro						,	15′886,7
	Date, 04/03/2015							
	Quantity Surveyor Arch. Jackie Bell							
	TO COLLECTION							